



Atlanta Office
 221 Armour Drive
 Atlanta, GA 30324
 P 404-745-7223
 F 404-327-5107
 atlpsiservice@dhpaces.com

Kansas City Office
 1901 E. 119th Street
 Olathe, KS 66061
 P 816-480-2601
 F 816-480-2612
 kcpsiservice@dhpaces.com

St. Louis Office
 12046 Lackland Rd
 St. Louis, MO 63146
 P 314-781-5200
 F 816-480-2612
 stlpsiservice@dhpaces.com

SOLD TO: City of Warrensburg, MO
 102 S Holden St
 Warrensburg, MO, 64093
 Gary Swanson

PROJECT: Parks Maintenance Building - 4 Cameras
QUOTE #: PQ#ARB7434A
PAGE: 6 Pages
DATE: 12/4/2021

REVISED
4/8/2022

Account Manager: Andy Baker

Cell: (816) 365-1680

Office: (816) 480-2643

DH Pace Systems Integration is pleased to quote you the following Scope of Work, all applicable taxes excluded:

DH Pace System Integration (PSI) will provide and install the below listed material:

Install (2) outdoor rated 4.0Mp dome cameras in the west and east garage area of the Parks Maintenance Building. Install a 180 degree multi-sensor camera on the south side of the building to view the parking lot and gas pump. Install a 270 degree multi-sensor camera on the southwest corner of the building to view the upper parking lot and gas pump. An 8 channel Avigilon recording appliance with 4Tb of storage will be installed in the IT area on the upper level. A CAT6 cable will be pulled from each camera to the IT Area through the office area and the open garage areas. Cable will be surface mounted and installed tight to the wall or ceilings. We will program the IP into each camera, program, aim and focus with the assistance of the IT Director.

CCTV

Quantity	Description of Material
Headend Equipment in IT Area	
1	HD Video Appliance 8-Port 4TB; NA - HD Video Appliance 8-Port 4TB; NA. ACC licenses sold separately
4	ACC 7 Enterprise Edition camera license
West Garage Camera (PM01)	
1	4.0 MP WDR, LightCatcher, Day/Night, Outdoor Dome, 3.3-9mm f/1.3 P-iris lens, Integrated IR, Next-Generation Analytics
100	CAT6 UNS SOL CMP ORG JKT 23-4P
East Garage Camera (PM02)	
1	4.0 MP WDR, LightCatcher, Day/Night, Outdoor Dome, 3.3-9mm f/1.3 P-iris lens, Integrated IR, Next-Generation Analytics
100	CAT6 UNS SOL CMP ORG JKT 23-4P
South Side 2nd Floor Camera (PM03)	
1	3x 5 MP, WDR, LightCatcher, 4mm, Camera Only
1	Pedant wall mount adapter. For use with H4 IR PTZ or H4A-MH-AD-PEND1 on H4 Multisensor.
1	Outdoor pendant mount adapter, must order one of IRPTZ-MNT-WALL1 or IRPTZ-MNT-NPTA1 and one of H4AMH-DO-COVR1 or H4AMH-DO
1	Dome bubble and cover, for outdoor surface mount or pendant mount, clear.
100	CAT6 UNS SOL CMP ORG JKT 23-4P
South Side West Corner Camera (PM04)	
1	3x 5 MP, WDR, LightCatcher, 2.8mm, Camera Only
1	Pedant wall mount adapter. For use with H4 IR PTZ or H4A-MH-AD-PEND1 on H4 Multisensor.
1	Outdoor pendant mount adapter, must order one of IRPTZ-MNT-WALL1 or IRPTZ-MNT-NPTA1 and one of H4AMH-DO-COVR1 or H4AMH-DO
1	Dome bubble and cover, for outdoor surface mount or pendant mount, clear.
1	Corner mount adapter for use with H4A-MT-WALL1, H4-BO-JBOX1, H4SL, H4F, H4 PTZ, H4 IR PTZ and H4 Multisensor cameras.
100	CAT6 UNS SOL CMP ORG JKT 23-4P



Atlanta Office
 221 Armour Drive
 Atlanta, GA 30324
 P 404-745-7223
 F 404-327-5107
 atlpsiservice@dhpaces.com

Kansas City Office
 1901 E. 119th Street
 Olathe, KS 66061
 P 816-480-2601
 F 816-480-2612
 kcpsiservice@dhpaces.com

St. Louis Office
 12046 Lackland Rd
 St. Louis, MO 63146
 P 314-781-5200
 F 816-480-2612
 stlpsiservice@dhpaces.com

SOLD TO: City of Warrensburg, MO
 102 S Holden St
 Warrensburg, MO, 64093
 Gary Swanson

PROJECT: Parks Maintenance Building - 4 Cameras
QUOTE #: PQ#ARB7434A
PAGE: 6 Pages
DATE: 12/4/2021

REVISED 4/8/2022

Account Manager: Andy Baker **Cell: (816) 365-1680** **Office: (816) 480-2643**

For us to complete our work on site in a timely manner, we will need the owner to provide the following items: access to all areas that we need to perform work; network connectivity/static IP address with subnet and gateway information; Owner provided material – (J-Hooks, patch panels and keystone jacks.)

Our proposal includes the following items: provide and install low voltage cabling; final cable terminations at field devices and headend locations; all installation is to be performed during normal weekday business hours;

Our proposal specifically excludes the following items: overtime or after normal working hours work; prevailing wage rates;

Please sign and either fax quote to Andy Baker at (816) 480-2612 or email it to us at : andy.baker@dhpaces.com **SYSTEM INSTALLATION INVESTMENT: \$ 10,456.50**

The proposal described herein, including all price(s) quoted, is made conditionally upon Seller's (1) verification of Buyer's credit status; and (2) Buyer's acceptance of any special payment made by Seller. To accept this Proposal, Buyer must date, sign and return the original copy hereof to Seller. Unless expressly disclosed and stated, the amount of any sales and use tax is not included in this proposal.

Parties agree that this proposal is submitted and accepted under the terms and conditions of the Avigilon Installation and Maintenance Agreement Dated September 7, 2021

Costs are currently rising at sudden and unpredictable rates. This proposal is based on current pricing from Sellers suppliers and includes all price increases and surcharges levied by those suppliers and known by Seller as of the date of this proposal. Seller reserves the right to require an approved change order before the order can be released into production to compensate for any supplier price increases or surcharges announced after the date of this Proposal and prior to the release of materials for fabrication. Seller will provide written documentation of the Supplier increase notice upon request. All Buyer Contracts shall include a provision to this affect.

PROPOSAL – SELLER

ACCEPTANCE - BUYER

By: _____
 Mark Elpers
 Senior Vice President

 Title

By: _____
 Park Director
 Date: _____
 Attest: _____

 Cindy Gabel, City Clerk